

PTO/SB/21 (09-04)


Approved for use through 07/31/2006. OMB 0651-0031


U.S. Patent and Trademark Office; U.S. DEPARTMENT OF COMMERCE

Under the Paperwork Reduction Act of 1995, no persons are required to respond to a collection of information unless it displays a valid OMB control number.

TRANSMITTAL FORM (to be used for all correspondence after initial filing)	Application Number	10/587,343	
	Filing Date	25 Jul 2006	
	First Named Inventor	Bin Xing, et al	
	Art Unit		
	Examiner Name		
Total Number of Pages in This Submission	32	Attorney Docket Number	42.P19574

ENCLOSURES (Check all that apply)		
<input type="checkbox"/> Fee Transmittal Form <input type="checkbox"/> Fee Attached <input type="checkbox"/> Amendment/Reply <input type="checkbox"/> After Final <input type="checkbox"/> Affidavits/declaration(s) <input type="checkbox"/> Extension of Time Request <input type="checkbox"/> Express Abandonment Request <input type="checkbox"/> Information Disclosure Statement <input checked="" type="checkbox"/> Certified Copy of Priority Document(s) <input type="checkbox"/> Reply to Missing Parts/Incomplete Application <input type="checkbox"/> Reply to Missing Parts under 37 CFR 1.52 or 1.53	<input type="checkbox"/> Drawing(s) <input type="checkbox"/> Licensing-related Papers <input type="checkbox"/> Petition <input type="checkbox"/> Petition to Convert to a Provisional Application <input type="checkbox"/> Power of Attorney, Revocation <input type="checkbox"/> Change of Correspondence Address <input type="checkbox"/> Terminal Disclaimer <input type="checkbox"/> Request for Refund <input type="checkbox"/> CD, Number of CD(s) _____ <input type="checkbox"/> Landscape Table on CD	<input type="checkbox"/> After Allowance Communication to TC <input type="checkbox"/> Appeal Communication to Board of Appeals and Interferences <input type="checkbox"/> Appeal Communication to TC (Appeal Notice, Brief, Reply Brief) <input type="checkbox"/> Proprietary Information <input type="checkbox"/> Status Letter <input checked="" type="checkbox"/> Other Enclosure(s) (please identify below): Return Receipt Postcard
Remarks		

SIGNATURE OF APPLICANT, ATTORNEY, OR AGENT		
Firm Name	BLAKELY, SOKOLOFF, TAYLOR & ZAFMAN, LLP 12400 Wilshire Boulevard, Seventh Floor, Los Angeles, CA 90025-1030	
Signature		
Printed name	Lester J. Vincent	
Date	September 5, 2006	Reg. No. 31,460

CERTIFICATE OF TRANSMISSION/MAILING		
I hereby certify that this correspondence is being deposited with the United States Postal Service on the date shown below with sufficient postage as first class mail in an envelope addressed to: Mail Stop PCT, Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450.		
Signature		
Typed or printed name	Theresa Joenks	Date 9/5/06

This collection of information is required by 37 CFR 1.5. The information is required to obtain or retain a benefit by the public which is to file (and by the USPTO to process) an application. Confidentiality is governed by 35 U.S.C. 122 and 37 CFR 1.11 and 1.14. This collection is estimated to 2 hours to complete, including gathering, preparing, and submitting the completed application form to the USPTO. Time will vary depending upon the individual case. Any comments on the amount of time you require to complete this form and/or suggestions for reducing this burden, should be sent to the Chief Information Officer, U.S. Patent and Trademark Office, U.S. Department of Commerce, P.O. Box 1450, Alexandria, VA 22313-1450. DO NOT SEND FEES OR COMPLETED FORMS TO THIS ADDRESS. SEND TO: Commissioner for Patents, P.O. Box 1450, Alexandria, VA 22313-1450.

If you need assistance in completing the form, call 1-800-PTO-9199 and select option 2.

中华人民共和国国家知识产权局
STATE INTELLECTUAL PROPERTY OFFICE
OF THE PEOPLE'S REPUBLIC OF CHINA



证 明
CERTIFICATE

本证明之附件是向中国专利局作为受理局提交的下列国际申请副本
IS TO CERTIFY THAT ANNEXED HERETO IS A TRUE COPY OF THE BELOW
IDENTIFIED INTERNATIONAL APPLICATION THAT WAS FILED WITH THE
CHINESE PATENT OFFICE AS RECEIVING OFFICE

申请号: PCT/CN2004/001221
INTERNATIONAL APPLICATION NUMBER
申请日: 28.10月 2004 (28.10.2004)
INTERNATIONAL FILING DATE
名称: INCREMENTAL PROVISIONING OF SOFTWARE
INVENTION

CERTIFIED COPY OF
PRIORITY DOCUMENT



中华人民共和国国家知识产权局局长
COMMISSIONER OF THE STATE INTELLECTUAL PROPERTY
OFFICE OF THE PEOPLE'S REPUBLIC OF CHINA

田力普

二零零六年七月二十七日
JULY 27, 2006

BEST AVAILABLE COPY

PCT REQUEST

Original (for SUBMISSION) - printed on 25.10.2004 03:28:27 PM

0	For receiving Office use only	
0-1	International Application No.	PCT/CN2004 / 0 0 1 2 2 1
0-2	International Filing Date	28 · 10月 2004 (28 · 10 · 2004)
0-3	Name of receiving Office and "PCT International Application"	RO/CN 中华人民共和国国家知识产权局 PCT International Application
0-4	Form - PCT/RO/101 PCT Request	
0-4-1	Prepared using	PCT-EASY Version 2.92 (updated 01.11.2003)
0-5	Petition The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty	
0-6	Receiving Office (specified by the applicant)	China Intellectual Property Office (RO/CN)
0-7	Applicant's or agent's file reference	047657 PC
I	Title of invention	INCREMENTAL PROVISIONING OF SOFTWARE
II	Applicant	
II-1	This person is:	applicant only
II-2	Applicant for	all designated States except US
II-4	Name	INTEL CORPORATION
II-5	Address:	2200 Mission College Boulevard Santa Clara, CA 95052 United States of America
II-6	State of nationality	US
II-7	State of residence	US
III-1	Applicant and/or inventor	
III-1-1	This person is:	applicant and inventor
III-1-2	Applicant for	US only
III-1-4	Name (LAST, First)	XING, Bin
III-1-5	Address:	Rm 502 No. 12, Lane 250 Lixilu, Shanghai China
III-1-6	State of nationality	CN
III-1-7	State of residence	CN

PCT REQUEST

Original (for SUBMISSION) - printed on 25.10.2004 03:28:27 PM

III-2	Applicant and/or inventor	
III-2-1	This person is:	applicant and inventor
III-2-2	Applicant for	US only
III-2-4	Name (LAST, First)	CHEN, Lechong
III-2-5	Address:	Rm 1003 No. 31 Lane 1555 Kaixuanbeilu, Shanghai China
III-2-6	State of nationality	CN
III-2-7	State of residence	CN
III-3	Applicant and/or inventor	
III-3-1	This person is:	applicant and inventor
III-3-2	Applicant for	US only
III-3-4	Name (LAST, First)	YU, Ke
III-3-5	Address:	Rm 402 No. 26 Gujinglu, Shanghai China
III-3-6	State of nationality	CN
III-3-7	State of residence	CN
III-4	Applicant and/or inventor	
III-4-1	This person is:	applicant and inventor
III-4-2	Applicant for	US only
III-4-4	Name (LAST, First)	MEI, Jianfeng
III-4-5	Address:	Rm 1204 Building 3, Lane 48 Jiaotongxilu, Shanghai China
III-4-6	State of nationality	CN
III-4-7	State of residence	CN
III-5	Applicant and/or inventor	
III-5-1	This person is:	applicant and inventor
III-5-2	Applicant for	US only
III-5-4	Name (LAST, First)	CHEN, Yi
III-5-5	Address:	Rm 1102 No. 36 Lane 177 Zhongshanbeiluzhenpinglu, Shanghai China
III-5-6	State of nationality	CN
III-5-7	State of residence	CN

PCT REQUEST

Original (for SUBMISSION) - printed on 25.10.2004 03:28:27 PM

IV-1	Agent or common representative; or address for correspondence The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as:	agent
IV-1-1	Name	SHANGHAI PATENT & TRADEMARK LAW OFFICE
IV-1-2	Address:	435 Guiping Road Shanghai 200233 China
IV-1-3	Telephone No.	86—21—64853500
IV-1-4	Facsimile No.	86—21—64828651
IV-1-5	e-mail	sptl@siit.intnet.com.cn
V	Designation of States	
V-1	Regional Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	<p>AP: BW GH GM KE LS MW MZ SD SL SZ TZ UG ZM ZW and any other State which is a Contracting State of the Harare Protocol and of the PCT</p> <p>EA: AM AZ BY KG KZ MD RU TJ TM and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT</p> <p>EP: AT BE BG CH&LI CY CZ DE DK EE ES FI FR GB GR HU IE IT LU MC NL PT RO SE SI SK TR and any other State which is a Contracting State of the European Patent Convention and of the PCT</p> <p>OA: BF BJ CF CG CI CM GA GN GQ GW ML MR NE SN TD TG and any other State which is a member State of OAPI and a Contracting State of the PCT</p>
V-2	National Patent (other kinds of protection or treatment, if any, are specified between parentheses after the designation(s) concerned)	<p>AE AG AL AM AT AU AZ BA BB BG BR BW BY BZ CA CH&LI CN CO CR CU CZ DE DK DM DZ EC EE EG ES FI GB GD GE GH GM HR HU ID IL IN IS JP KE KG KP KR KZ LC LK LR LS LT LU LV MA MD MG MK MN MW MX MZ NA NI NO NZ OM PG PH PL PT RO RU SC SD SE SG SK SL SY TJ TM TN TR TT TZ UA UG US UZ VC VN YU ZA ZM ZW</p>

PCT REQUEST

Original (for SUBMISSION) - printed on 25.10.2004 03:28:27 PM


V-5	Precautionary Designation Statement In addition to the designations made under items V-1, V-2 and V-3, the applicant also makes under Rule 4.9(b) all designations which would be permitted under the PCT except any designation(s) of the State(s) indicated under item V-6 below. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit.		
V-6	Exclusion(s) from precautionary designations	NONE	
VI	Priority claim	NONE	
VII-1	International Searching Authority Chosen	China Intellectual Property Office (ISA/CN)	
VIII	Declarations	Number of declarations	
VIII-1	Declaration as to the identity of the inventor	-	
VIII-2	Declaration as to the applicant's entitlement, as at the international filing date, to apply for and be granted a patent	-	
VIII-3	Declaration as to the applicant's entitlement, as at the international filing date, to claim the priority of the earlier application	-	
VIII-4	Declaration of inventorship (only for the purposes of the designation of the United States of America)	-	
VIII-5	Declaration as to non-prejudicial disclosures or exceptions to lack of novelty	-	
IX	Check list	number of sheets	electronic file(s) attached
IX-1	Request (including declaration sheets)	5	-
IX-2	Description	13	-
IX-3	Claims	6	-
IX-4	Abstract	1	EZABST00.TXT
IX-5	Drawings	3	-
IX-7	TOTAL	28	
	Accompanying items	paper document(s) attached	electronic file(s) attached
IX-8	Fee calculation sheet	✓	-
IX-17	PCT-EASY diskette	-	Diskette
IX-19	Figure of the drawings which should accompany the abstract	3	
IX-20	Language of filing of the international application	English	
X-1	Signature of applicant, agent or common representative		
X-1-1	Name	SHANGHAI PATENT & TRADEMARK LAW OFFICE	

PCT REQUEST

Original (for SUBMISSION) - printed on 25.10.2004 03:28:27 PM

FOR RECEIVING OFFICE USE ONLY

10-1	Date of actual receipt of the purported international application	2004.10月28日
10-2	Drawings:	
10-2-1	Received	
10-2-2	Not received	
10-3	Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application	
10-4	Date of timely receipt of the required corrections under PCT Article 11(2)	
10-5	International Searching Authority	ISA/CN
10-6	Transmittal of search copy delayed until search fee is paid	



FOR INTERNATIONAL BUREAU USE ONLY

11-1	Date of receipt of the record copy by the International Bureau	
------	--	--

PCT (ANNEX - FEE CALCULATION SHEET)Original (for **SUBMISSION**) - printed on 25.10.2004 03:28:27 PM

(This sheet is not part of and does not count as a sheet of the international application)

0	For receiving Office use only	PCT/CN2004 / 0 0 1 2 2 1		
0-1	International Application No.			
0-2	Date stamp of the receiving Office	2004.10月 2004 (2 8 . 1 0 . 2 0 0 4)		
0-4	Form - PCT/RO/101 (Annex)			
0-4-1	PCT Fee Calculation Sheet Prepared using	PCT-EASY Version 2.92 (updated 01.11.2003)		
0-9	Applicant's or agent's file reference	047657 PC		
2	Applicant	INTEL CORPORATION, et al.		
12	Calculation of prescribed fees	fee amount/multiplier	Total amount (Equivalent in local currency of CHF)	Total amounts (CNY)
12-1	Transmittal fee T	⇒		500
12-2-1	Search fee S	⇒		1,500
12-2-2	International search to be carried out by	CN		
12-3	International fee			
	Basic fee (first 30 sheets) b1	1,400 CHF		
12-4	Remaining sheets	0		
12-5	Additional amount (X)	15 CHF		
12-6	Total additional amount b2	0 CHF		
12-7	b1 + b2 = B	1,400 CHF		
12-8	Designation fees			
	Number of designations contained in international application	100		
12-9	Number of designation fees payable (maximum 5)	5		
12-10	Amount of designation fee (X)	0 CHF		
12-11	Total designation fees D	0 CHF		
12-12	PCT-EASY fee reduction R	-100 CHF		
12-13	Total international fee (B+D-R) I	⇒	1,300	
12-17	TOTAL FEES PAYABLE (T+S+I+P)	⇒	1,300	2,000
12-19	Mode of payment	authorization to charge deposit account		
12-20	Deposit account instructions			
	The receiving Office:	China Intellectual Property Office (RO/CN)		
12-20-1	Authorization to charge the total fees indicated above.	✓		
12-20-2	Authorization to charge any deficiency or credit any overpayment in the total fees indicated above.	✓		
12-20-3	Authorization to charge the fee for priority document.	✓		
12-21	Deposit account No.	SPTL		
12-22	Date	25 October 2004 (25.10.2004)		

PCT (ANNEX - FEE CALCULATION SHEET)

Original (for SUBMISSION) - printed on 25.10.2004 03:28:27 PM



12-23	Name and signature	SHANGHAI PATENT & TRADEMARK LAW OFFICE
-------	--------------------	--

VALIDATION LOG AND REMARKS

13-2-3	Validation messages Names	Green? Applicant 1.:Telephone No. missing
		Green? Applicant 1.:Facsimile No. missing
		Yellow Applicant 2.:Postal code missing
		Yellow Applicant 3.:Postal code missing
		Yellow Applicant 4.:Postal code missing
		Yellow Applicant 5.:Postal code missing
		Yellow Applicant 6.:Postal code missing
13-2-7	Validation messages Contents	Yellow! The power of attorney or a copy of the general power of attorney will need to be furnished unless all applicants sign the request form.
13-2-8	Validation messages Fees	Green? Please confirm that fee schedule utilized is the latest available
		Yellow Fee amount(s) should not equal zero.
13-2-9	Validation messages Payment	Green? Please ensure that you have a valid deposit account with the receiving Office selected.
13-2-1 0	Validation messages Annotate	Green? The name of the person signing the request or/and the capacity in which the person signs has/have not been indicated. Please be informed that some receiving Offices require that this information be present along with the signature.
13-2-1 1	Validation messages For receiving Office/International Bureau use only	Green? Verify electronic data for consistency against printed form.

Incremental Provisioning Of Software

Field of the Invention

[0001] The present disclosure relates generally to the field of data processing, and more particularly to the incremental provisioning of software for a processing system.

Background

[0002] Manually setting up a data processing system is time consuming work. For instance, it may take hours to install and configure the operating system (OS), drivers, and user applications desired for a particular personal computer (PC).

[0003] In certain situations, automation may be used to expedite the process. For instance, if many processing systems with identical hardware are to receive identical software components and configurations, one system to serve as a model may be manually loaded with the desired software and configured. A disk image from the model system may then be copied to each of the other systems, to provision those systems with the same software and configuration as the model system. The processing systems to be provisioned may be referred to as managed systems or managed platforms. The model image may be stored on a processing system operating as a server. Each managed system may also include firmware that runs in a preboot execution environment (PXE), retrieves the model image from the server, and loads the model image into a local hard disk drive. The managed system may then launch an OS from the local hard disk drive.

[0004] However, such a model disk image may easily exceed ten gigabytes (GB). Consequently, even though it may be unnecessary to manually install and configure individual software components, a significant amount of time is nevertheless required to provision a system from a model disk image.

[0005] Once the model image has been loaded, that image may be modified by subsequent use of the managed system. For instance, a user may intentionally or inadvertently modify the configuration settings, install new software, cause the system to receive a virus, or otherwise alter the original image. Such

modifications may adversely effect how the processing system functions for subsequent users, or otherwise cause undesirable results.

[0006] Two types of adapter cards, known as hard drive (HD) protection cards or HD recovery cards, have been designed to protect the data on a hard disk drive from modification. The first type of HD protection card divides a hard disk drive into a visible partition and a hidden partition. The HD protection card then intercepts every IDE write command directed to the visible partition, and redirects those writes to the hidden partition. Subsequent reads involving the data written to the hidden partition are then also redirected to the hidden partition. Alternatively, the HD protection card can allow the write commands to modify the data in the visible partition, but only after copying the original data from the visible partition to the hidden partition.

[0007] After an HD recovery card has processed write transactions as indicated above, the user may decide whether or not to accept the modifications permanently. Alternatively, the HD recovery card may accept policy settings that cause the processing system to revert to the original data whenever the system is rebooted. For example, if writes were redirected to the hidden partition, the HD recovery card may discard or disregard the data in the hidden partition after the reboot. If writes were applied to the original partition after copying the original data to the hidden partition, the HD recovery card may copy the original data from the hidden partition back to the visible partition.

[0008] A Chinese company known as Nanjing HardSoft advertises the second type of HD protection card. Like the first type of card, the second type also uses space on the hard drive to store both the original data and the modified data. However, the second type of card may not require the use of a hidden partition on that disk drive. Instead, the second type of card may simply utilize unused blocks in the visible partition.

[0009] Both types of cards may track the changes in a modification log. The modification log may be stored in the hard drive itself, or possibly in flash memory or some other type of storage onboard the HD protection card.

[0010] Both types of HD protection cards may reduce the runtime performance of the processing system by approximately 20%. For instance, system performance is reduced significantly when original data is copied to a

second location on the hard disk before a write is allowed to modify the data in the first location, and when reads and writes are redirected. In addition, since space on the hard drive is required for the original data and the modified data, the hard disk capacity available to the user may be reduced to approximately 50% of the actual capacity of the hard disk.

Brief Description Of The Drawings

[0011] The features and advantages of the present invention will become apparent from the appended claims and the following detailed description of one or more example embodiments, in which:

[0012] FIG. 1 is a block diagram depicting an example embodiment of a suitable data processing environment in which certain aspects of the invention may be implemented;

[0013] FIG. 2 is a flowchart illustrating a process for implementing incremental provisioning, in accordance with an example embodiment of the present invention; and

[0014] FIG. 3 is a block diagram depicting incremental provisioning operations performed according to an example embodiment of the present invention.

Detailed Description

[0015] The present disclosure describes one or more example embodiments of methods and apparatuses which support incremental provisioning of software. Such methods and apparatuses may be used to provision or reprovision a data processing system, or a multitude of data processing systems, more quickly than is possible using conventional means.

[0016] FIG. 1 and the following discussion are intended to provide a general description of a suitable environment in which certain aspects of the present invention may be implemented. As used herein, the terms "processing system" and "data processing system" are intended to broadly encompass a single machine, or a system of communicatively coupled machines or devices operating together. Exemplary processing systems include, without limitation, distributed computing systems, supercomputers, computing clusters, mainframe

computers, mini-computers, client-server systems, personal computers, workstations, servers, portable computers, laptop computers, tablet processing systems, telephones, personal digital assistants (PDAs), handheld devices, entertainment devices such as audio and/or video devices, and other devices for processing or transmitting information.

[0017] The data processing environment of FIG. 1, for example, may include a processing system 20 that includes one or more processors or central processing units (CPUs) 22 communicatively coupled to various other components via one or more buses 28 or other communication conduits or pathways. Such components may include one or more volatile or non-volatile data storage devices, such as random access memory (RAM) 24 and read-only memory (ROM) 25. For purposes of this disclosure, the term "ROM" may be used in general to refer to non-volatile memory devices such as erasable programmable ROM (EPROM), electrically erasable programmable ROM (EEPROM), flash ROM, flash memory, etc. CPU 22 may also be communicatively coupled to mass storage devices, such as one or more integrated drive electronics (IDE), small computer systems interface (SCSI), or other types of hard disk drives 40. Other types of mass storage devices and storage media that may be used by processing system 20 may include floppy-disks, optical storage, tapes, flash memory, memory sticks, digital video disks, biological storage, etc.

[0018] The components coupled to processor 22 may also include one or more PCI root bridges and one or more PCI-to-PCI bridges. One or more of the above bridges and buses may be used to connect processor 22, either directly or indirectly, with storage devices and with additional components, such as one or more input/output (I/O) devices, ports, or controllers 26. Such devices may include a video controller, a SCSI controller, a network controller, a universal serial bus (USB) controller, a keyboard controller, etc. In one embodiment, one or more devices may be implemented as embedded controllers, using components such as programmable or non-programmable logic devices or arrays, application-specific integrated circuits (ASICs), embedded computers, smart cards, and the like. For instance, a PCI root bridge may be implemented as an embedded device, residing on a system backplane or motherboard.

[0019] Processing system 20 may be controlled, at least in part, by input from conventional input devices, such as a keyboard 32, a mouse, etc., and/or by directives received from one or more remote data processing systems 50, interaction with a virtual reality (VR) environment, biometric feedback, or other input sources or signals. Processing system 20 may send output to components such as a display device 30, remote data processing system 50, etc.

Communications with remote data processing system 50 may travel through any suitable communications medium. Processing systems may be interconnected by way of a physical and/or logical network 36, such as a local area network (LAN), a wide area network (WAN), an intranet, the Internet, etc. Communications involving network 36 may utilize various wired and/or wireless short range or long range carriers and protocols, including radio frequency (RF), satellite, microwave, Institute of Electrical and Electronics Engineers (IEEE) 802.11, Bluetooth, optical, infrared, cable, laser, etc.

[0020] The invention may be described by reference to or in conjunction with associated data including instructions, functions, procedures, data structures, application programs, etc. which when accessed by a machine result in the machine performing tasks or defining abstract data types or low-level hardware contexts. The data may be referred to in general as software, and it may be stored in volatile and/or non-volatile data storage.

[0021] For example, ROM 25 may include firmware instructions 70 for establishing a firmware environment 44 when processing system 20 is booted. Alternatively, some or all of the firmware instructions may be retrieved from one or more remote sources, such as remote data processing system 50.

[0022] A model for an interface between platform firmware and higher-level software such as operating systems was recently announced. That model is known as the Extensible Firmware Interface (EFI). Version 1.10 of the EFI Specification, dated December 1, 2002, may be obtained from www.intel.com/technology/efi/main_specification.htm. The EFI specification defines a set of standard interfaces and structures to be provided by low-level platform firmware, for use in loading additional firmware and booting the OS. Platform frameworks based on the EFI model, such as the Intel® Platform Innovation Framework for EFI, are expected, within the next few years, to

supplant frameworks based on the basic input/output system (BIOS) model as the frameworks of choice for designing, building, and operating data processing systems. The Intel® Platform Innovation Framework for EFI includes low-level firmware which provides boot and runtime service calls that are available to the operating system and its loader. In one embodiment of the present invention, firmware instructions 70 operate in accordance with the EFI specification.

[0023] Firmware instructions 70 may include numerous modules that are loaded into RAM 24 during the boot process before an OS 62 is launched. Those firmware modules may include a provisioning module or agent 58. Provisioning agent 58 may also be referred to as incremental provisional agent 58. Processing system 20 may also include a write monitoring module 46. In one embodiment, write monitoring module 46 is implemented as part of OS 62, for instance as part of a device driver 64 for managing reads from and writes to devices such as hard disk drive 40. In alternative embodiments, write monitoring module 46 may be implemented as software outside of OS 62, or as hardware or a combination of hardware and software, for instance as part of a disk drive controller 56 associated with hard disk drive 40, as suggested by the dashed box near the center of FIG. 1. Additional details concerning provisioning agent 58 and write monitoring module 46 are provided below.

[0024] FIG. 2 is a flowchart illustrating a process for implementing incremental provisioning, in accordance with an example embodiment of the present invention. The illustrated process may begin with processing system 20 beginning a boot process after having been powered on or reset, for example. The initial stages of the boot process may include loading and executing firmware instructions 70 to establish a preboot execution environment (PXE), as depicted at block 202. As indicated at block 204, processing system may then load a provisioning agent 58 into RAM 24. In one embodiment, processing system 20 obtains provisioning agent 58 from remote data processing system 50. Provisioning agent 58 may be designed to operate in the preboot execution environment. Additional components, such as a transmission control protocol (TCP) driver, may also be obtained from a local or remote source. Processing system 20 may then launch or start provisioning agent 58, as indicated at block 206.

[0025] As indicated at block 210, provisioning agent 58 may then determine whether a disk write log file 48 for processing system 20 exists. Disk write log file 48 may also be referred to as write log 48 or log file 48. As described in greater detail below, write log 48, if it exists, may include information that identifies which blocks within hard disk drive 40 have been modified. However, if write log 48 does not exist, provisioning agent 58 may conclude that processing system 20 has not yet been configured to support incremental provisioning, and provisioning agent 58 may therefore perform the initial provisioning of processing system 20. For instance, provisioning agent 58 may obtain a disk image from remote processing system 50, and provisioning agent 58 may load that image into hard disk drive 40 in processing system 20, as depicted at block 212.

[0026] For purposes of this disclosure, the term "disk image" refers a data image that contains or provides an exact, byte-for-byte copy of data on the subject drive (i.e., the drive from which the image was derived). Disk images may be created, for example, using tools such as the disk imaging utility distributed by Symantec Corporation under the trademark NORTON GHOST. A disk image may provide or constitute a copy of an entire physical hard disk drive, a copy of a logical drive, or a copy of a drive partition, for example.

[0027] As illustrated in FIG. 1, in the example embodiment, remote processing system 50 may include one or more storage devices 54 that contain a copy of a disk image to be used for provisioning platforms such as processing system 20. Such an image may be referred to in general as provisionable software 52.

[0028] Processing system 50 may be considered one possible embodiment of a remote management device or remote management system. Since the content of provisionable software 52 typically will not be affected by operations at processing system 20, provisionable software 52 may also be considered a backup or archive copy of the initial software content of processing system 20. Once provisionable software 52 has been copied into processing system 20, the copy in hard disk drive 40 may be referred to a provisioned software 42. Accordingly, processing system 20 may also be referred to as target processing system 20, managed processing system 20, or local processing system 20. Provisioned software 42 may include, for example, OS 62, one or more user

applications 66 (e.g., a web browser program, a word processing application, etc.), information pertaining to configuration settings for the software and/or hardware in processing system 20, and other data.

[0029] Referring again to FIG. 2, in conjunction with provisioning

5 processing system with the original disk image, provisioning agent 58 may create write log 48, as indicated at block 214. In one embodiment, write log 48 resides in processing system 20. Write log 48 may reside in hard disk drive 40 or in other non-volatile storage such as EEPROM or flash memory. In alternative
10 embodiments, write log 48 may reside outside of processing system 20, for example in remote processing system 50, as indicated by the dashed box toward the bottom of FIG. 1.

[0030] As depicted at block 220 in FIG. 2, after creating write log 48 or determining that write log 48 already exists, provisioning agent 58 may determine whether write log 48 identifies any blocks from hard disk drive 40 as having been
15 modified since the last time processing system 20 was provisioned. Blocks that are identified as having been modified may also be referred to as dirty blocks. If write log 48 does not identify any dirty blocks, provisioning agent 58 may conclude that provisioned software 42 matches provisionable software 52, and may therefore allow processing system 20 to boot OS 62, as indicated at block 226. In
20 the example embodiment, the OS 62 is part of provisioned software 42.

[0031] However, if write log 48 includes one or more entries identifying one or more dirty blocks, provisioning agent 58 obtains a clean copy of one of those blocks from provisionable software 52 in remote processing system 50, and overwrites the dirty block in hard disk drive 40 with the clean block, as indicated at
25 block 222. At block 224 provisioning agent 58 may then update write log 48 so that write log 48 no longer identifies the block in question as dirty. As indicated by the arrow returning to block 220 from block 224, provisioning agent 58 may continue to obtain clean blocks from remote processing system 50 and copy those blocks over the dirty blocks in hard disk drive 40 until the original content has
30 been returned to each dirty block.

[0032] In one embodiment, provisioning agent 58 utilizes native provisioning infrastructure in an EFI-compliant firmware environment to facilitate the original provisioning operations and the subsequent incremental provisioning

operations. Other resources may be used to provision and/or incrementally reprovision managed processing systems in alternative embodiments.

[0033] Once provisioned software 42 has been restored to its original condition or determined to be clean, provisioning agent 58 may allow processing system 20 to boot OS 62, as indicated at block 226. Once processing system 20 boots to OS 62, write monitoring module 46 may begin monitoring all write commands addressed to hard disk drive 40. As indicated at blocks 230 and 232, whenever write monitoring module 46 detects a write command addressed to hard disk drive 40, write monitoring module 46 makes sure that write log 48 includes an entry to identify to block being modified or written to.

[0034] For instance, write monitoring module 46 may maintain a bit map corresponding to the blocks in hard disk drive 40, with write monitoring module 46 setting bits as appropriate to indicate whether respective blocks have been logged as dirty. Accordingly, write monitoring module 46 may update write log 48 only when the block being addresses has not already been flagged as dirty in the bitmap. To improve performance, the bitmap may reside in RAM 24. In order not to miss any modifications, the logging operation may be completed before the write operation is executed and/or before the bitmap is updated. To minimize the amount of time required to complete the logging operation, the log may be stored in a faster storage medium, such as in registers on some dedicated hardware device. Alternatively, for write logs kept in remote processing systems, high-speed reliable connections to the remote systems may be used to transmit log updates.

[0035] Referring again to FIG. 1, arrows 80 and 82 illustrate that provisioning agent 58 may retrieve, from remote processing system 50, the necessary data to load and restore provisioned software 42 in processing system 20. The provisioning and reprovisioning operations may therefore be managed completely or primarily from within firmware environment 44. Further, the provisioning and reprovisioning operations may be completely automated, with those operations being managed with regard to a local or remote write log 48. Arrows 84 and 86 illustrate that write monitoring module 46 may update write log 48 to identify the blocks in hard disk drive 40 being modified by OS 62.

39

[0036] FIG. 3 is a block diagram depicting incremental provisioning operations performed according to an example embodiment of the present invention. For purposes of illustration, FIG. 3 depicts ten individual blocks within hard disk drive 40, and ten corresponding blocks in the model image 52 in remote processing system 50. In processing system 20 the slanted lines within blocks A and B indicate that those two blocks are identified as dirty in write log 48. In remote processing system 50 the dots in the corresponding blocks A and B indicate that those blocks contain a backup copy of the content that was originally provisioned into blocks A and B of target processing system 20. Arrows 110A and 110B indicate that, when provisioning agent 58 runs in processing system 20, provisioning agent 58 will replace the modified content of dirty blocks A and B with clean content from storage device 54 in remote processing system 50.

[0037] Also, in FIG. 3, the blocks in hard disk drive 40 that are not filled with slanted lines represent blocks that were provisioned and are still clean.

Consequently, in the illustrated embodiment, provisioning agent 58 overwrites only blocks A and B in hard disk drive 40. Processing system 20 may therefore be reprovisioned in a fraction of the time that would be required to provision an entire disk image. When implemented in an EFI-compliant platform, the invention may provide EFI-based incremental provisioning in a networked environment. For instance, the invention may provide incremental data collection and restoration.

[0038] In the example embodiment, OS 62 addresses hard disk drive 40 by reference to blocks or block addresses. For instance, each block in hard disk drive 40 may be identified by a unique logical block address (LBA). OS 62 may use those LBAs in write commands directed to hard disk drive 40, and write monitoring module 46 may use those LBAs, or values based on those LBAs, to identify dirty blocks in write log 48. In alternative embodiments, the mass storage device holding the software configuration in the managed processing system may use different types of storage subdivisions, an operating system in the managed processing system may address the storage device by reference to other types of addresses or indexes, and the write monitoring module may use other types of indexes or addresses to keep track of which blocks or subdivisions have been modified.

[0039] In an example embodiment, the platform firmware does not require a file system driver. In addition, the teachings herein could be used to manage storage devices that employ any suitable file system, including without limitation, file allocation table (FAT) file systems, NT file systems (NTFSs), and future file systems. Such file systems may be supported without requiring a file system driver in the platform firmware. The teachings may also be implemented without requiring any additional hardware components in the managed processing systems.

[0040] The teachings of the present disclosure may be used to advantage in any environment that includes a processing system to be restored to an original software configuration. For instance, a private or public entity or organization may wish to deploy numerous processing systems for utilization by individual users. Those processing systems may all have identical or substantially similar hardware configurations, and the above process may be used to provide each of those systems with the same software configuration from a central server or a group of servers.

[0041] After the initial software configuration is loaded, multiple users may utilize the managed processing systems. For instance, a first user may use one of the systems, and then a second user may use that same system. For purposes of this document, the period of time spent by a user interacting with a processing system may be referred to as a user session or a session of interaction. A user session may be terminated by resetting or rebooting the processing system, or by any other suitable event. In case any changes may have been made to the software configuration when the first user was interacting with the system, the system may be rebooted after the first user has finished his or her session of interaction and before the second user starts his or her session. In accordance with the teachings herein, during the reboot process the original content may be automatically restored to any modified storage blocks in the system. For instance, the modified blocks may be restored after the OS terminates for one user session but before the OS is launched again for the next user session. The desired software configuration may thus be rapidly restored to the system in preparation for the next session of interaction with a user.

[0042] For example, if an organization wished to equip a number of Internet cafes with processing systems to be used by the general public, the teachings herein could be used to rapidly restore each processing system to an original software configuration by simply rebooting each processing system between each user session. According to one embodiment, through use of incremental provisioning, it may be possible to restore a disk image within two minutes or less after one user checks out and before the next user checks in. A similar usage model may be used in the education sector and in other public and private organizations.

[0043] In light of the principles and example embodiments described and illustrated herein, it will be recognized that the illustrated embodiments can be modified in arrangement and detail without departing from such principles. For instance, although one or more example embodiments have been described, for purposes of illustration, with regard to software to be incrementally provisioned to a hard disk drive, alternative embodiments include embodiments in which software, configuration data, or other information associated with establishing a particular environment on a target platform is incrementally provisioned into any suitable type of mass storage device.

[0044] [0001] Also, an alternative embodiment may involve replacing the model disk image in the management server with a new model image that incorporates changes such as updates to software or configuration settings. The management server may then push the new model image, or the modified portions of that image, to the managed clients. The clients may then utilize incremental re-provisioning to maintain the updated image using a process such as the one described above with regard to FIG. 2, in which the clients initiate the transmission of the backup data.

[0045] Although the foregoing discussion has focused on particular embodiments, other configurations are contemplated. In particular, even though expressions such as "in one embodiment," "in another embodiment," or the like are used herein, these phrases are meant to generally reference embodiment possibilities, and are not intended to limit the invention to particular embodiment configurations. As used herein, these terms may reference the same or different embodiments that are combinable into other embodiments.

[0046] Similarly, although example processes have been described with regard to particular operations performed in a particular sequence, it will be apparent to those of ordinary skill in the art that numerous modifications to the processes could be applied to derive numerous alternative embodiments of the present invention. For example, alternative embodiments may include processes that use fewer than all of the disclosed operations, processes that use additional operations, processes that use the same operations in a different sequence, and processes in which the individual operations disclosed herein are combined, subdivided, or otherwise altered.

[0047] Alternative embodiments of the invention also include machine accessible media encoding instructions for performing the operations of the invention. Such embodiments may also be referred to as program products. Such machine accessible media may include, without limitation, storage media such as floppy disks, hard disks, CD-ROMs, ROM, and RAM; as well as communications media such as antennas, wires, optical fibers, microwaves, radio waves, and other electromagnetic or optical carriers. Accordingly, instructions and other data may be delivered over transmission environments or networks in the form of packets, serial data, parallel data, propagated signals, etc., and may be used in a distributed environment and stored locally and/or remotely for access by single or multi-processor machines.

[0048] It should also be understood that the hardware and software components depicted herein represent functional elements that are reasonably self-contained so that each can be designed, constructed, or updated substantially independently of the others. In alternative embodiments, many of the components may be implemented as hardware, software, or combinations of hardware and software for providing the functionality described and illustrated herein.

[0049] In view of the wide variety of useful permutations that may be readily derived from the example embodiments described herein, this detailed description is intended to be illustrative only, and should not be taken as limiting the scope of the invention. What is claimed as the invention, therefore, is all implementations that come within the scope and spirit of the following claims and all equivalents to such implementations.

4/1

What is claimed is:

1. A method comprising:

5 copying a disk image to a hard disk drive on a managed platform, wherein the disk image is copied from a model disk image stored on a storage device of a remote management system;

during a user session on the managed platform, monitoring write commands from an operating system of the managed platform;

10 in response to detecting write commands from the operating system that address blocks of the hard disk drive, automatically updating a write log to identify the blocks addressed by the write commands;

after completion of the user session, automatically determining whether one or more blocks of the hard disk drive were modified, based at least in part on the write log; and

15 in response to determining that at least one block in the hard disk drive was modified, automatically restoring original contents to the modified block during a boot process for the managed platform by overwriting the modified block with corresponding backup data from the model disk image.

20

2. A method according to claim 1, wherein the operation of copying a disk image to a hard disk drive on a managed platform comprises:

provisioning the managed platform with software by automatically loading the disk image into the managed platform from the remote management system during a boot process for the managed platform.

25

3. A method according to claim 1, wherein the disk image comprises an image of a disk partition.

30 4. A method according to claim 1, further comprising:

terminating the operating system on the managed platform before restoring the original contents to the modified block from the remote management system.

5. A method according to claim 4, further comprising:
 launching the operating system on the managed platform after restoring the original contents to the modified block from the model disk image.
- 5 6. A method comprising:
 during a user session on a platform, in response to write commands addressing blocks of a storage device in the platform, automatically updating a write log to identify the blocks addressed by the write commands;
 after completion of the user session, automatically identifying one or more
 10 modified blocks in the storage device, based at least in part on the write log; and
 in response to identifying at least one modified block in the storage device, automatically replacing data in the modified block with backup data from a different storage device.
- 15 7. A method according to claim 6, further comprising:
 in advance of the user session, provisioning the platform with software by copying a disk image to the storage device in the platform from a model disk image stored on the different storage device.
- 20 8. A method according to claim 7, wherein the operation of copying a disk image comprises copying the disk image from a remote data processing system.
9. A method according to claim 6, wherein the storage device in the platform comprises a hard disk drive.
- 25 10. A method according to claim 6, wherein the operation of automatically replacing data in the modified block with backup data from a different storage device comprises:
 automatically restoring the modified block during a boot process for the
 30 platform by overwriting the modified block with corresponding backup data from a model disk image.
11. A method according to claim 6, further comprising:

terminating an operating system on the platform before replacing the data in the modified block with backup data from the different storage device.

12. A method according to claim 11, further comprising:

5 launching the operating system on the platform after replacing the data in the modified block with backup data from the different storage device.

13. An apparatus comprising:

a machine accessible medium; and

10 instructions encoded in the machine accessible medium, wherein the instructions, when executed by a processing system, perform operations comprising:

during a user session on the processing system, in response to write commands addressing blocks of a storage device in the processing system,
15 automatically updating a write log to identify the blocks addressed by the write commands;

after completion of the user session, automatically identifying one or more modified blocks in the storage device, based at least in part on the write log; and

in response to identifying at least one modified block in the storage device,
20 automatically replacing data in the modified block with backup data from a different storage device.

14. An apparatus according to claim 13, wherein the instructions comprise firmware instructions to execute before the processing system boots to an
25 operating system.

15. An apparatus according to claim 13, wherein the instructions perform further operations comprising:

in advance of the user session, provisioning the processing system with
30 software by copying a disk image to the storage device in the processing system from a model disk image stored on the different storage device.

16. An apparatus according to claim 15, wherein the instructions cause the processing system to copy the disk image from a remote data processing system.

17. An apparatus according to claim 13, wherein the storage device in the
5 processing system comprises a hard disk drive.

18. An apparatus according to claim 13, wherein the operation of automatically replacing data in the modified block with backup data from a different storage device comprises:

10 automatically restoring the modified block during a boot process for the processing system by overwriting the modified block with corresponding backup data from a model disk image.

19. An apparatus according to claim 13, wherein the instructions perform
15 further operations comprising:
terminating an operating system on the processing system before replacing the data in the modified block with backup data from the different storage device.

20. An apparatus according to claim 19, wherein the instructions perform
20 further operations comprising:
launching the operating system on the platform after replacing the data in the modified block with backup data from the different storage device.

21. A processing system comprising:
25 a machine accessible medium;
a storage device;
a processor;
one or more communication paths to couple the processor with the machine accessible medium and the storage device; and
30 instructions encoded in the machine accessible medium, wherein the instructions, when executed by the processor, perform operations comprising:

- during a user session on the processing system, in response to write commands addressing blocks of the storage device, automatically updating a write log to identify the blocks addressed by the write commands;
- after completion of the user session, automatically identifying one or more modified blocks in the storage device, based at least in part on the write log; and
- 5 in response to identifying at least one modified block in the storage device, automatically replacing data in the modified block with backup data from a different storage device.
- 10 22. A processing system according to claim 21, wherein the instructions comprise firmware instructions to execute before the processing system boots to an operating system.
23. A processing system according to claim 21, wherein the instructions
- 15 perform further operations comprising:
- in advance of the user session, provisioning the processing system with software by copying a disk image to the storage device in the processing system from a model disk image stored on the different storage device.
- 20 24. A processing system according to claim 23, wherein the instructions cause the processing system to copy the disk image from a remote data processing system.
- 25 25. A processing system according to claim 24, further comprising the remote data processing system.
26. A processing system according to claim 21, wherein the storage device in the processing system comprises a hard disk drive.
- 30 27. A processing system according to claim 21, wherein the operation of automatically replacing data in the modified block with backup data from a different storage device comprises:

automatically restoring the modified block during a boot process for the processing system by overwriting the modified block with corresponding backup data from a model disk image.

- 5 28. A processing system according to claim 21, wherein the instructions perform further operations comprising:

terminating an operating system on the processing system before replacing the data in the modified block with backup data from the different storage device.

- 10 29. A processing system according to claim 28, wherein the instructions perform further operations comprising:

launching the operating system on the platform after replacing the data in the modified block with backup data from the different storage device.

ABSTRACT

Methods and apparatuses provide for incremental provisioning of software
5 for a processing system. For instance, a processing system may include a
machine accessible medium and a processor in communication with the machine
accessible medium. In addition, instructions encoded in the machine accessible
medium may cause the processing system to automatically determine whether a
storage device in the processing system includes modified blocks, based at least
10 in part on a write log file that identifies blocks that were modified during a user
session on the processing system. In response to identifying at least one
modified block in the storage device, the processing system may automatically
replace data in the modified block with backup data from a different storage
device. Other embodiments are described and claimed.

15




FIG. 1




FIG. 2




FIG. 3

**This Page is Inserted by IFW Indexing and Scanning
Operations and is not part of the Official Record**

BEST AVAILABLE IMAGES

Defective images within this document are accurate representations of the original documents submitted by the applicant.

Defects in the images include but are not limited to the items checked:

- ☐ **BLACK BORDERS**
- ☐ **IMAGE CUT OFF AT TOP, BOTTOM OR SIDES**
- ☐ **FADED TEXT OR DRAWING**
- ☐ **BLURRED OR ILLEGIBLE TEXT OR DRAWING**
- ☐ **SKEWED/SLANTED IMAGES**
- ☐ **COLOR OR BLACK AND WHITE PHOTOGRAPHS**
- ☐ **GRAY SCALE DOCUMENTS**
- ☐ **LINES OR MARKS ON ORIGINAL DOCUMENT**
- ☐ **REFERENCE(S) OR EXHIBIT(S) SUBMITTED ARE POOR QUALITY**
- ☐ **OTHER:** _____

IMAGES ARE BEST AVAILABLE COPY.

As rescanning these documents will not correct the image problems checked, please do not report these problems to the IFW Image Problem Mailbox.